

B. Performance Guarantee & Functional Test

B.1. Performance Guarantee Test

B.1.1. PG Test - CO₂ Capture, Compression and Storage Block:

- a) PG Test shall be carried out to demonstrate the 50 TPD i.e 2.08 TPH of CO₂ production capacity while simultaneously meeting the quality of CO₂ on dry basis as mentioned elsewhere under the head 'Design Considerations'.
- b) PG Test shall be carried out after completion of 'Trial Operation' and 'Functional Tests'
- c) Liquidated damage for deviation in performance shall be computed as under:
 - i) Deviation in performance = [(Tested capacity of CO₂ Production - Guaranteed capacity of CO₂ Production) / Guaranteed capacity of CO₂ Production]
 - ii) Liquidated damage = 0.5 x (Contract Value) x (Deviation in performance)
- d) PG Test duration shall be at least 24 continuous hours.

B.1.2. PG Test - Carbonated Brick (C-Brick) Manufacturing Block:

- a) PG Test shall be carried out to demonstrate i) C-Brick Manufacturing Capacity of 2,00,000 Nos/Day (Minimum) and ii) Compressive Strength of C-Brick > 7.5 Mpa.
- b) PG Test shall be carried out after completion of 'Trial Operation' and 'Functional Tests'
- c) Liquidated damage for deviation in performance shall be computed as under:
 - iii) Deviation in performance = [(Tested capacity of C-Brick Production - Guaranteed capacity of C-Brick Production) / Guaranteed capacity of C-Brick Production]
 - iv) Liquidated damage = 0.5 x (Contract Value) x (Deviation in performance)
- d) PG Test duration shall be at least 24 continuous hours.

B.1.3. PG Test - General:

- a) Bidder shall provide the PG Test procedure for approval of NTPC.
- b) PG test shall be carried out as per the approved PG Test procedure. PG test procedure shall be finalized within 120 days from the date of Notification of Award.
- c) The Bidder shall be responsible for providing all material, equipment and manpower, specified or otherwise, which are required to carry out PG Test.
- d) There shall be no incentive / reward in case of positive performance deviation i.e. when tested capacity of C-brick production is more than the guaranteed capacity.